

Engineering & Related Services

BUILDING RELATIONSHIPS. DESIGNING SOLUTIONS.

ACT 167 IMPLEMENTATION WORKSHOP ORDINANCE ENFORCEMENT



STORMWATER MANAGEMENT

Keys to Success:



Education

Staff Training Know the Ordinance Public Outreach

Consistency

Standard reviews & inspections

Documentation

Make & keep records



AGENDA















IMPACTS from Land Development & Poorly Managed Stormwater

- Compacted Soils
- Less Evapotranspiration
- Less Groundwater Recharge
- Increased Runoff Volume
- Faster Conveyance of Water
- Increased Frequency of Runoff Events
- Erosion and Stream Channel Impacts
- Decreased Baseflow
- Pollution and Thermal Impacts
- Impacted Aquatic Life

Stormwater regulations

<u>Clean Water Act</u>: NPDES Program is established; Focus is primarily on POTWs and industrial discharges

Water Quality Act: Amends CWA and calls for a phased approach; SW now explicitly regulated

<u>Stormwater Phase 1 Rule</u>: NPDES program covers (i) "medium & large" MS4s (ii) Earth Disturbances > 5 ac (iii) 10 categories of industrial activity

Stormwater Phase 2 Rule: NPDES program expands to cover "small" MS4s & Earth Disturbances > 1 ac

Energy Independence and Security Act: Requires federal agencies to use LID on projects > 5,000 sf

Stormwater regulations

Conventional Stormwater Management

- Controls Peak Rate of Runoff to Existing Conditions for Large Storms (theoretically)
- No Runoff Volume Control
- No NPS Pollutants Control

Conventional Stormwater Management

Detention Basins may only slow the runoff

Still have...

- Flooding
- Polluted Runoff
- Eroded Streams

Perhaps Worse

Concentration of flow

New Approach to SWM

Non-structural BMP's

First – Protect & Preserve

- Avoid & Minimize Impacts
- Riparian Buffers/Woodlands

Maximize Green Infrastructure

- Conservation Corridors
- Green belts

New Approach to SWM

Non-structural BMP's

Reduce Impervious Cover – Cluster & Concentrate Development

New Approach to SWM

Non-structural BMP's

NEILTRATION

Slow down runoff

BIO-SWALE/

SWM on small lots

Lot = 0.1 acre (4050 sf)

Impervious: 2360 sf

- 1470 sf home
- 240 sf deck
- 500 sf driveway
- 150 sf walkway

AN EMPLOYEE-OWNED COMPANY

Butler County's 2010 Act 167

Model Ordinance.

STORMWATER MANAGEMENT MODEL ORDINANCE

Implementing the Requirements of the

Butler County Stormwater Management Plan

ORDINANCE NO. _____ OF_____

_____, BUTLER COUNTY, PENNSYLVANIA

Adopted at a Public Meeting Held on _____, 2010

HIRG Herbert, Rowland & Grubic, Inc. Engineering & Related Services AN EMPLOYEE-OWNED COMPANY

Article I - General Provisions

- Section 101. Short Title
- Section 102. Statement of Findings
- Section 103. Purpose
- Section 104. Statutory Authority
- Section 105. Applicability
- Section 106. Repealer
- Section 107. Severability
- Section 108. Compatibility with Other Requirements
- Section 109. Duty of Persons Engaged in the Development of Land
- Section 110. Municipal Liability Disclaimer

REVIEW WITH SOLICITORS!

Section 109. Duty of Persons Engaged in the Development of Land

Notwithstanding any provision(s) of this Ordinance, including exemptions, any landowner or any person engaged in the alteration or development of land which may affect stormwater runoff characteristics shall implement such measures as are reasonably necessary to prevent injury to health, safety, or other property. Such measures also shall include actions as are required to manage the rate, volume, direction, and quality of resulting stormwater runoff in a manner which otherwise adequately protects health, property, and water quality.

Section 110. Municipal Liability Disclaimer

A. Neither the granting of any approval under this Ordinance, nor the compliance with the provisions of this Ordinance, or with any condition imposed by a municipal official hereunder, shall relieve any person from any responsibility for damage to persons or property resulting there from, or as otherwise imposed by law nor impose any liability upon the Municipality for damages to persons or property.

B. The granting of a permit which includes any storm water management facilities shall not constitute a representation, guarantee or warranty of any kind by the Municipality, or by an official or employee thereof, of the practicability or safety of any structure, use or other plan proposed, and shall create no liability upon or cause of action against such public body, official or employee for any damage that may result pursuant thereto.

Article II – Definitions

Agricultural Activity: ...construction of new buildings or impervious area is not considered an agricultural activity.

Impervious Area: A surface that prevents the infiltration of water into the ground.

Regulated Activities: Any earth disturbance activities or any activities that involve the alteration or development of land in a manner that may affect stormwater runoff.

Article III - Stormwater Management Standards

- Section 301. General Requirements
- Section 302. Exemptions
- Section 303. Waivers
- Section 304. Volume Controls
- Section 305. Rate Controls
- Section 306. Sensitive Areas and Stormwater Hotspots

Article III - Stormwater Management Standards

Section 301. General Requirements

- F. Impervious Areas:
 - 1. The measurement of impervious areas shall include all of the impervious areas in the total proposed development, even if development is to take place in stages.
 - 2. For developments taking place in stages, the entire development plan must be used in determining conformance with this Ordinance.
 - 3. [OPTIONAL] For projects that add impervious area to a developed parcel, to the maximum extent practicable and at the discretion of the Municipal Engineer, the total impervious area on the parcel may be subject to the requirements of this Ordinance.

Model Ordinance - EXEMPTIONS

New Impervious Area ^{1, 2} (square footage)	Applicant Must Provide					
0 – 2,500						
2,500 < 5,000	Documentation of new impervious surfaces ³					
> 5,000	Rate Controls, Volume Controls & SWM Site Plan					
NOTES:	NOTES:					
¹ New Impervious Area since the date of Adoption of this Ordinance.						
² Gravel in existing condition shall be considered pervious and gravel in proposed condition shall be considered impervious.						
³ The Small Project Storr	nwater Management Application included in					

Appendix E **shall** be used to document new impervious surfaces.

Model Ordinance - EXEMPTIONS

302.E. Single Family Residential Exemption

- Single Family Residential activities are exempt from these requirements provided the construction:
 - 1. Comply with Sections 302.A, 302.B, and 302.C
 - 2. Buildings setback 75' from downstream property lines
 - 3. Driveways:

- Discharge onto pervious surface w/gravel strip or other spreading device.
- Max 1,000 sf of paved surface may discharge to any one point.
 - Length of flow on the pervious must exceed the length of the paved surface flow.

Model Ordinance – Additional Provisions

SECTION 306. Sensitive Areas and Stormwater Hotspots

ADDED PERFORMANCE STANDARDS

- 1. Sensitive areas have the potential to endanger a water supply. These areas consist of the delineated 1-year zone of contribution and direct upslope areas tributary to the water supply wells.
- 2. Stormwater Hotspots are projects that have a high potential to endanger local water quality, and could potentially threaten ground water reservoirs. The PADEP wellhead protection contaminant source list shall be used as a guide in these determinations. Industrial manufacturing site and hazardous material storage areas must provide NPDES SIC codes.

Model Ordinance – VOLUME CONTROL

Sizing Criteria	Description of Stormwater Sizing Criteria				
Design Method (CG1)Storm	Regulation of the 2-year storm event: -No increase in total runoff volume for the 2-yr/24-yr event -Consider existing non-forest pervious area as meadow -20% of existing impervious area considered as meadow				
Simplified Method (CG2)	Regulation of stormwater runoff from new impervious (1 ac max): -capture of first 2" of runoff -1" of captured runoff shall be permanently removed -1/2" of captured runoff shall be infiltrated				
Water Quality Calculations	Where infiltration is not possible or desirable (document justification) -Specific BMP's for Pollution Prevention to reduce Total Suspended Solids (TSS) 85% Total Phosphate (TP) 85% Total Nitrate (NO ₃) 50%				

Article IV – E&S STANDARDS [OPTIONAL]

Section 401. Erosion And Sedimentation Requirements During Earth Disturbance Activities

> E&S Standards to reinforce the importance of BMP's during the construction process.

ARTICLE V – Protected Watersheds Standards

Due Diligence Review in Protected Watershed Areas

AN EMPLOYEE-OWNED COMPANY

Article VI – RIPARIAN BUFFER STANDARDS [OPTIONAL]

SECTION 601. RIPARIAN BUFFER REQUIREMENTS SECTION 602. RIPARIAN BUFFER EASEMENTS

Riparian Buffers

- Require natural areas adjacent to streams
- Use of areas adjacent to streams
- Refer to DEP's new Chapter 102
 Requirements

Article VII – DESIGN CRITERIA

SECTION 701. Design Criteria For Stormwater Management & Drainage Facilities [LARGELY OPTIONAL]

SECTION 702. Calculation Methodology

SECTION 703. Downstream Hydraulic Capacity Analysis

Standards are recommended so that everyone is using the same

Article VIII - SWM Site Plan Requirements

SECTION 801. General Requirements SECTION 802. SWM Site Plan & Report Contents SECTION 803. SWM Site Plan & Report Submission SECTION 804. SWM Site Plan & Report Review SECTION 805. Modification Of Plans SECTION 806. Resubmission Of Disapproved SWM Site Plan & Report SECTION 807. Authorization To Construct And Term Of Validity SECTION 808. Record Drawings, Completion & Final Inspection

Article IX – EASEMENTS

SECTION 901. Easements

- Requirements for SWM Facilities
- If diffused flow is concentrated, downstream easement required.

Article X – Maintenance Responsibilities

SECTION 1001. FINANCIAL GUARANTEE

110% Bond; As-Builts; Final Inspection

SECTION 1002. MAINTENANCE RESPONSIBILITIES

- Owner provided; Municipal rights; record as covenant w/land
- SECTION 1003. MAINTENANCE AGREEMENT FOR PRIVATELY OWNED STORMWATER FACILITIES
- O&M Agreement

Article XI – Inspections

SECTION 1101. SCHEDULE OF INSPECTIONS

- 1. Annually for the first 5 years following construction.
 - 2. Once every 3 years thereafter.
 - 3. During or immediately after a 10-yr storm.

SECTION 1102. RIGHT-OF-ENTRY

Municipal rights

Model Ordinance ARTICLE XII – ENFORCEMENT AND PENALTIES

SECTION 1201. NOTIFICATION

SECTION 1202. ENFORCEMENT

SECTION 1203. PUBLIC NUISANCE

SECTION 1204. SUSPENSION AND REVOCATION

SECTION 1205. PENALTIES

SECTION 1206. APPEALS

Article XIII – PROHIBITIONS

SECTION 1301. Prohibited Discharges and Connections

What you can connect to SWM

SECTION 1302. Roof Drains

Discharge to vegetated surface

SECTION 1303. Alteration of BMPs

Can't change BMP once approved

Article VIII - Fees and Expenses

Section 1401. General - review fees paid by applicant

Section 1402. Expenses Covered by Fees

Administration, review, inspections, enforcement

Section 1403. Recording of Approved SWM Site Plan & Related Agreements

- SWM Site Plan
- O&M Agreement
- Easements
- Riparian buffers

Appendices

APPENDIX A – Operation And Maintenance Agreement

APPENDIX B – Low Impact Development Practices

APPENDIX C – Stormwater Management Design Criteria

APPENDIX D – Review Fee Reimbersement Agreement

APPENDIX E – Small Project Swm Plan Application

APPENDIX F – Release Rate Map

IMPLEMENTATION

Models to consider:

MODEL	DESCRITION
Individual Municipal	Each municipality passes, implements, and enforces the SWM ordinance individually.
Multi-Municipal	Several municipalities cooperate through a new, or existing, service-sharing agreement (COG, Sewage Association, etc.)
County Service Provider	County department, or office, (e.g. County Planning Entity or County Conservation District) provides SWM ordinance implementation and enforcement services to municipalities.

IMPLEMENTATION - Administration

Information tracked:	 Project status Construction & Post Construction Inspections Enforcement Actions Complaints Completion
	 Size threshold for plan review? Pre-project meetings conducted with developer? Engineering approval? Criteria checklist used? BMPs adequately incorporated into the plan to address erosion control, sediment control, housekeeping? Design specifications & details for all BMPs included on the plans? Standards conditions include E&S or stormwater provisions?

Engineering & Related Services AN EMPLOYEE-OWNED COMPANY

IMPLEMENTATION - Administration

SMALL PROJECT SWM PLAN

Small Project SWM Plan

[Municipality] Small Project Stormwater Management Application

Per [municipality]'s Act 167 Stormwater Management Ordinance, a stormwater management plan is required whenever more than 2,500 square feet of impervious surface is proposed. Impervious surfaces are areas that prevent the infiltration of water into the ground and shall include, but not be limited to, roofs, patios, garages, storage sheds and similar structures, and any new streets or sidewalks.

To Calculate Impervious Surfaces Please Complete This Table								
Surface Type	Length	х	Width	=	Proposed Impervious Area			
Building		х		=				
(area per aownspout)		х		=				
		х		=				
		х		=				
Driveway		х		=				
		х		=				
		х		=				
Parking Areas		х		=				
		х		=				
		х		=				
Patios/Walks		х		=				
		х		=				
		x		=				
		x		=				
Other		х		=				
		х		=				
		х		=				
Total Imperviou	s Surface Area to be n	nan	aged (sum of all area	as)				

If the Total Impervious Surface Area is **LESS THAN 2,500 Square Feet**, a Stormwater Management Plan **IS NOT** required for this regulated activity. Please read, acknowledge and sign below.

If the Total Impervious Surface Area is MORE THAN 2,500 Square Feet, complete the rest of the Application.

Municipality] may request additional information and/or SWM for any reason.

Property Owner Acknowledges that submission of inaccurate information may result in a stop work order or permit revocation. Acknowledgement of such is by signature below. I declare that I am the owner or owner's legal representative. I further acknowledge that the information provided is accurate and employees of [municipality] are granted access to the above described property for review and inspection as may be required.

Owner

Date:

Simpler Process using Application

2,500 sf threshold for Documentation (could be for Volume Control)

Small Project SWM Plan

CREDITS

Credit 1: DISCONNECTION OF IMPERVIOUS AREA

When runoff from impervious areas is directed to a pervious area that allows for infiltration, filtration, and increased time of concentration, all or parts of the impervious areas may qualify as Disconnected Impervious Area (DIA). Using the criteria below, determine the portion of the impervious area that can be excluded from the calculation of total impervious area.

Criteria: An impervious area is considered to be completely or partially disconnected if it meets the requirements listed below

- rooftop area draining to a downspout is ≤500 sf
- paved area draining to a discharge is ≤1,000 sf
- flow path of paved impervious area is not more than 75'
- soil at discharge is not designated as hydrologic soil group "D"
- flow path at discharge area has a positive slope of ≤5%
- gravel strip or other spreading device is required at paved discharges.

* Flow path cannot include impervious surfaces and must be at least 15 feet from any impervious surfaces

Reduce size of Surfaces that need treatment with no cost BMP's (Credits)

	Calculate DIA Credit & Required Capture Volume								
Surface Type	Proposed Impervious Area (from previous sheet)	x	DIA Credit Factor	=	Impervious Area to be managed	÷		=	Required Capture Volume (ft ³)
Building		Х		=		÷	6	=	
(area per downspout)		Х		=		÷	6	=	
		х		=		÷	6	=	
		х		=		÷	6	=	
Driveway		х		=		÷	6	=	
		х		=		÷	6	=	
		х		=		÷	6	=	
Parking Areas		х		=		÷	6	=	
		х		=		÷	6	=	
		х		=		÷	6	=	
Patios/Walks		х		=		÷	6	=	
		х		=		÷	6	=	
		х		=		÷	6	=	
		х		=		÷	6	=	
Other		х		=		÷	6	=	
		х		=		÷	6	=	
		х		=		÷	6	=	
•				•		•	•		

AN EMPLOYEE-OWNED COMPANY

Total Req'd Capture Volume

Length of	DIA
Pervious Flow	Credit
Path from	Factor
discharge point *	
(ft)	
0 - 14	1.0
15 – 29	0.8
30 - 44	0.6
45 - 59	0.4
60 - 74	0.2
75 or more	0

Small Project SWM Plan

Credit 2: TREE PLANTING

Perhaps the best BMP is a tree as they intercept rainfall, increase evapotranspiration and increase time of concentration. A portion of the required capture volume can be reduced provided the criteria are met.

CREDITS

Deciduous Trees	Evergreen Trees
6 ft ³ per tree planted	10 ft ³ per tree planted

Criteria

To receive credit for planting trees, the following must be met:

- Trees must be native species (see below), minimum 2" caliper and 6 feet tall (min).
- Trees shall be adequately protected during construction.
- Trees shall be maintained until redevelopment occurs.
- No more than 25% of the runoff volume can be mitigated through the use of trees.
- Dead trees shall be replaced within 6 months.
- Non-native species are not applicable.

Reduce size of BMP's with common, low cost BMP's

Enter the volumes into the Small Project SWM Plan Worksheet on the next sheet.

Native Species Trees (Common Name)

- Blackgum
- Arrow-wood, southern
- Box-elder
- Maple, (red or silver)
- Birch, (river or gray)
- Ironwood
- Hickory, sweet pignut or shag-bark
- Cedar, (Atlantic white or eastern red)
- Beech, American
- Ash, (white, black or green)
- Holly, American
- Tuliptree

- Sycamore, American
- Cotton-wood, eastern
- Aspen, big-tooth or quaking
- Cherry, black
- Oak, (white, swamp white, scarlet, pin, willow, red)
- Willow, black
- Bald Cypress
- Basswood, American
- Serviceberry, (downy or shadbush)
- Redbud, eastern
- Dogwood, flowering
- Magnolia, sweetbay
- Pine, (pitch or eastern white)

Herbert, Rowland & Grubic, Inc. Engineering & Related Service: AN EMPLOYEE-OWNED COMPAN

Small Project SWM Plan

Small Project SWM Plan Worksheet

Based upon the information you have provided a **Stormwater Plan IS Required** for this development activity. The Stormwater Management Ordinance developed through the Erie County Act 167 Stormwater Management Plan regulates compliance requirements for Stormwater Management in this jurisdiction. A complete copy of the Plan can be found on the Erie County Planning website.

Regulated activities shall be conducted only after [municipality] approves a stormwater management plan. The Erie County Act 167 Stormwater Management Plan will assist you in preparing the necessary information and plans for [municipality] to review and approve. This document will constitute an approved plan if all of the relevant details are to be installed in their entirety AND no part of the stormwater system adversely affects any other property, nor adversely affect any septic systems or drinking water wells on this, or any other, parcel. If an alternative system is to be used a plan will need to be submitted to [municipality] for approval. A design by a qualified professional may be required for more complex sites.

PLEASE INITIAL BELOW TO INDICATE THE STORMWATER MANAGEMENT PLAN FOR THIS SITE

Minimum Control #2: Source Control of Pollution

Minimum Control #3: Preservation of Natural Drainage Systems and Outfalls

The relevant details from *Erie County Act 167 Stormwater Management Plan* will be installed in their entirety AND the system will be located as not to adversely affect other property, nor any septic systems or drinking water wells on this, or any other, parcel.

To meet this requirement, the following will be installed and maintained:

Capture Volume to be managed (ft ³)		Conversion	Surface Area of BMPs (ft ²)
By Rain Garde 6" ponding; 2' s	il depth X	1.20	
Dry Well or Infi 2½' aggregate	ration Trench x	1.25	
Total		Total	

In lieu of meeting the above, an alternative and/or professional design is attached for approval AND the system will be located as not to adversely affect other property, any septic systems or drinking water wells on this, or any other, parcel.

Site Sketch Plan showing:

- Property lines with dimensions
 - Proposed buildings with dimensions
- Proposed septic system, if applicable
- Proposed well site, if applicable
- Proposed impervious surfaces with dimensions

 Proposed stormwater management system(s)

Operation and Maintenance Agreement

Condition on approval - The stormwater management plan must be fully implemented prior to a request for final inspection of the building or zoning permit.

Acknowledgement - By executing below, the Owner acknowledges the following:

- I declare that I am the owner of the property.
- The information provided is accurate.
- I further acknowledge that municipal representatives are granted access to the above described property for review and inspection as may be required.

Date:

Documentation w/ O&M Agreement

INSPECTIONS

IMPLEMENTATION – Construction Inspection

Inspector Training/Knowledge

- 1. Is the inspector knowledgeable about:
 - Erosion and sediment control BMPs,
 - Stormwater/pollution prevention BMPs,
 - Legal authority (ordinances)?
- 2. Is the inspector familiar with the requirements in the State stormwater construction general permit?
- 3. What type of stormwater training did the inspector receive? When, and how often?

IMPLEMENTATION – Construction Inspection

Inspection Procedures

- 1. Is a checklist used during the inspection?
- 2. Is the inspector aware of previous stormwater inspection results at this site?
- 3. Does the inspector review the approved plans required to be at the construction site?
- 4. Does the inspector walk the entire site and inspect all points of discharge?
- 5. Does the inspection address:
 - E&S control
 - Waste management practices
 - Non-stormwater discharges?
- 6. Are inspection findings documented in writing and presented to the site contact?

IMPLEMENTATION – Construction Inspection

FIELD OBSERVATION REPORT

Municipality:	Report Number:		
Project:	HRG Project Number:		
Owner:	Time Charge:		
Property ID:	Date	[Pick the date] Time	9:
Weather Clear Snow Warm Overcast Foggy Hot Rain Cold	Site Conditions Clear Dusty Muddy Temperature Range	Day ☐ Monday ☐ Tuesday ☐ Wednesda	☐ Thursday ☐ Friday ay ☐
Reason for site visit: Routine Visit Con	tractor/Developer Request 🛛 Municip Phone:	ality Request 🛛	
Contact Person:	E-Mail:		

Persons Contacted:

W	ork Force:			E	quipment at Site	•
	Classification	[Contractor X]	[Contractor Y]	[Contractor Z]		
	Supervisor					

Work Observed:

Items Discussed:

Nonconforming Work Reported this Date to Contractor:

Remarks:

FIELD OBSERVATION REPORT

Municipality:		Report Number:		
Project:		HRG Project Number:		
Owner:		Time Charge:		
Property ID:		Date	[Pick the date] Time:	
<u>Weather</u> Clear Snow Overcast Foggy Rain Cold] Warm] Warm] Hot] Muddy] Tempe	itions Dusty Comparison Dusty Prature Range	<u>Dav</u> ☐ Monday ☐ Tuesday ☐ Wednesday	☐ Thursday ☐ Friday □
Reason for site visit:	utine Visit 🔲 Contractor/Deve	eloper Request 🗌 Municipa	ality Request	
Contractor Company:		Phone:		
Contact Person:		E-Mail:		
Persons Contacted:				
	Herbert, Rowland & Grubic, Inc. Engineering & Related Services	DESIGNING SOLU	נאטווז.	

AN EMPLOYEE-OWNED COMPANY

Work Force:			E	quipment at Site)
Classification	[Contractor X]	[Contractor Y]	[Contractor Z]		
Supervisor					

Work Observed:

Items Discussed:

Nonconforming Work Reported this Date to Contractor:

Remarks:

IMPLEMENTATION – Enforcement

FOLLOW THE ORDINANCE!

Municipality has the <u>duty</u> and right to enforce ordinance provisions

IMPLEMENTATION – Enforcement

VIOLATIONS

Investigate reported or observed violations

- Speak to person alleged to be in violation
- 2. Observe discharge area, storm drain system, surface waters
- 3. Take pictures
- 4. Obtain additional information
- 5. Explain findings to alleged violator
- 6. Document all findings in writing

IMPLEMENTATION – Enforcement

Notice of Violation

- Location of violation
- Description of each violation
- Enforcement Action and potential penalties
- Deadline to correct violation
- Suggest requiring a written response from violator

Suspension And Revocation

- Suspend for violation (can reinstate)
- Revoke = new approval

Appeals

- To Municipality within 30 days;
- Butler Court within 30 days

MS4 – Minimum Control Measures

- MCM #1 Public Education and Outreach
- MCM #2 Public Involvement and Participation
- MCM #3 Illicit Discharge Detection and Elimination
- MCM #4 Construction Site Stormwater Runoff Control
- MCM #5 Post-Construction Stormwater Management in New and Re-Development Activities
- MCM #6 Pollution Prevention / Good Housekeeping

MCM #4: Construction Site Stormwater Runoff Control

BMP #1 – Develop your program consisting of all procedures necessary to comply with the requirements of this MCM.

BMP #2 – Enact, implement, and enforce an ordinance to require the implementation of erosion and sediment control BMPs, as well as sanctions to ensure compliance.

BMP #3 – Develop and implement requirements for construction site operators to control waste at the construction site that may cause adverse impacts to water quality.

BMP #4 – Develop and implement procedures for the receipt and consideration of public inquiries, concerns, and information submitted by the public regarding local construction activities.

MCM #5 - Post-Construction Stormwater Management in New and Re-Development Activities

BMP #1 – Develop a written procedure that describes how the permittee will address all required components of this plan.

BMP #2 – Require the implementation of a combination of structural and/or nonstructural BMPs that are appropriate to the local community, that minimize water quality impacts, and that are designed to maintain predevelopment runoff conditions.

BMP #3 – Ensure that controls are installed that will prevent or minimize water quality impacts.

BMP #4 – The permittee should enact, implement, and enforce an ordinance or other regulatory mechanism to address PCSW runoff from new and redevelopment projects, as well as sanctions and penalties associated with noncompliance, to the extent allowable under state law.

BMP #5 - Develop and implement measures to encourage and expand the use of Low Impact Development (LID) in new and redevelopment. Measures also should be included to encourage retrofitting LID into existing development.

BMP #6 – Ensure adequate operation and maintenance of all postconstruction stormwater management BMPs installed at all qualifying development or redevelopment projects (including those owned or operated by the permittee).

Herbert, Rowland & Grubic, Inc. Engineering & Related Services AN EMPLOYEE-OWNED COMPANY DESIGNING SOLUTIONS.

IMPLEMENTATION – Construction Inspection

MCM #4 – CONSTR	UCTIC	IN SITE SW R	UNOFF	CON	ITROL	Approval No.	Approval Date	
E/S Approval	Obtair	ned		N/.	A			
NPDES Permit Obtained		N/A		A				
E/S BMPs Onsite: Date Installed		Properly Functioning		erly oning	Comments			
Inlot Protection			Yes		No			
Slit Fence	닏							
Silt Sock								
RCE								
Sediment Basin								
Sediment Trap								
Truck Washout								
	1							
MCM #5 - POST CO	NSTR	UCTION SW (PCSM) A		VITIES			
PCSM BMPs Onsite): 	Date Properly		erly	Comments			
		Installed	FL	Incti	oning No	-		
Swales								
Rain Garden	H							
Bio Retention								
Detention Basin	H							
Underground Basin	H							
Chabigroana Babin	H							
	H			_				
				_				
	H							
	닏							
Comments:								

Attachments

Signed by:				Date:	
Copies: 🗌 Municipality 🗌 Owner	Contractor	Consultants	□	. 🗆	_ 🗌 File
$C: \label{eq:calibration} C: eq:cal$	Page 2 of 2				

MCM #4 – CONSTRUCTION SITE SW RUNOFF CONTROL					Approval No.	Approval Date
E/S Approval Obtained		N/A				
NPDES Permit Obtained		N/A				
E/S BMPs Onsite:		Date Installed	Properly Functioning		Comments	
	1		Yes	No		
Inlet Protection						
Silt Fence						
Silt Sock						
RCE						
Sediment Basin						
Sediment Trap						
Truck Washout						
	-		-	-		

		•		•	
MCM #5 - POST CONSTRUCTION SW (PCSM) ACTIVITIES					
PCSM BMPs Onsite:		Date Properly Installed Functioning		perly ioning	Comments
			Yes	No	
Swales					
Rain Garden					
Bio Retention					
Detention Basin					
Underground Basin					
Comments:					

Questions

Douglas E. Weikel, PE Director of Civil Engineering

Cell: 814-280-0227

Office: 814-238-7117

dweikel@hrg-inc.com

Ben Gilberti, PE Regional Service Manager

814-883-9339

724-779-4777

bgilberti@hrg-inc.com

www.hrg-inc.com

